ISSAI100

Mark-up of proposed changes relating to Quality Management In connection with revision of ISSAI 140

FUNDAMENTAL PRINCIPLES OF PUBLIC-SECTOR AUDITING



INTOSAI Standards are issued by the International Organisation of Supreme Audit Institutions, INTOSAI, as part of the INTOSAI Framework of Professional Pronouncements. For more information visit www.issai.org



INTOSAI, 2019

1) Endorsed as Basic Principles in Government Auditing in 2001

2) Revised and renamed Fundamental Principles of Public-Sector Auditing in 2013

3) With the establishment of the Intosai Framework of Professional Pronouncements (IFPP), editorial changes were made in 2019

4) With the adoption of ISSAI 150 on auditor competence supplements were made in 2022

ISSAI 100 is available in all INTOSAI official languages: Arabic, English, French, German and Spanish

TABLE OF CONTENTS

INTRODUCTION	4	
PURPOSE AND AUTHORITY OF THE ISSAIS	6	
FRAMEWORK FOR PUBLIC-SECTOR AUDITING	9	
MANDATE	9	
PUBLIC-SECTOR AUDITING AND ITS OBJECTIVES	10	
TYPES OF PUBLIC-SECTOR AUDIT	11	
ELEMENTS OF PUBLIC-SECTOR AUDITING	13	
THE THREE PARTIES	13	
SUBJECT MATTER, CRITERIA AND SUBJECT MATTER INFORMATION	14	
TYPES OF ENGAGEMENT	14	
CONFIDENCE AND ASSURANCE IN PUBLIC-SECTOR AUDITING	15	
PRINCIPLES OF PUBLIC-SECTOR AUDITING	17	
ORGANISATIONAL REQUIREMENTS	18	
GENERAL PRINCIPLES	19	
PRINCIPLES RELATED TO THE AUDIT PROCESS	23	

INTRODUCTION

- Professional standards and guidelines are essential for the credibility, quality and professionalism of public-sector auditing. The International Standards of Supreme Audit Institutions (ISSAIs) developed by the International Organisation of Supreme Audit Institutions (INTOSAI) aim to promote independent and effective auditing by supreme audit institutions (SAIs).
- The ISSAIs support the members of INTOSAI in the development of their own professional approach in accordance with their mandates and with national laws and regulations.
- 3) The ISSAIs form part of the INTOSAI Framework of Professional Pronouncements (IFPP). Within this framework, the INTOSAI Principles (INTOSAI-P) contain the framework's founding principles and core principles that set out prerequisities for the proper functioning of SAIs. The International Standards of Supreme Audit Institutions (ISSAIs) address the conduct of audits and include generally-recognised professional principles that underpin the effective and independent auditing of public-sector entities.
- 4) INTOSAI Guidance (GUIDs) also form part of the IFPP. They provide guidance to support SAIs and individual auditors in enhancing organizational performance and implementing and applying the ISSAIs in practice.

- 5) The ISSAI 100 *Fundamental Principles of Public-Sector Auditing* draw and elaborate on *INTOSAI-P 1 The Lima Declaration* and provide an authoritative international frame of reference defining public-sector auditing. The full set of ISSAIs is based on these principles.
- 6) ISSAI 100 *Fundamental Principles of Public-Sector Auditing* provides detailed information on:
 - the purpose and authority of the ISSAIs;
 - the framework for public-sector auditing;
 - the elements of public-sector auditing;
 - the principles to be applied in public-sector auditing.

PURPOSE AND AUTHORITY OF THE ISSAIS

7) ISSAI 100 Fundamental Principles of Public-Sector Auditing establishes fundamental principles which are applicable to all public-sector audit engagements, irrespective of their form or context. ISSAI 200 Financial Audit Principles, ISSAI 300 Performance Audit Principles and ISSAI 400 Compliance Audit Principles build on and further develop the principles to be applied in the context of financial, performance and compliance auditing respectively. They should be applied in conjunction with the principles set out in ISSAI 100. The principles in no way override national laws, regulations or mandates or prevent SAIs from carrying out investigations, reviews or other engagements which are not specifically covered by the existing ISSAIs.

8) The Fundamental Principles of Public-Sector Auditing (ISSAI 100) and the Financial, Performance and Compliance Auditing Principles¹ that flow from this can be used to establish authoritative standards in three ways:

- as a basis on which SAIs can develop standards;
- as a basis for the adoption of consistent national standards;
- as a basis for adoption of the ISSAIs.

SAIs may choose to compile a single standard-setting document, a series of such documents or a combination of standard-setting and other authoritative documents.

SAIs should declare which standards they apply when conducting audits, and this declaration should be accessible to users of the SAI's reports. Where the standards are based on several sources taken together, this should also be stated. SAIs are encouraged to make such declarations part of their audit reports; however, a more general form of communication may be used.

1 ISSAIs 200, 300 and 400

9) An SAI may declare that the standards it has developed or adopted are based on or are consistent with the principles of the ISSAIs only if the standards fully comply with all relevant principles in ISSAIs 100, 200, 300 and 400.

Audit reports may include a reference to the fact that the standards used were based on or consistent with the ISSAI or ISSAIs relevant to the audit work carried out. Such reference may be made by stating:

... We conducted our audit[s] in accordance with [standards], which are based on [or consistent with] ISSAI 100 Fundamental Principles of Public-Sector Auditing [and the principles of ISSAI 200 Financial Audit Principles / ISSAI 300 Performance Audit Principles / ISSAI 400 Compliance Audit Principles] of the International Standards of Supreme Audit Institutions.

In order to properly adopt or develop auditing standards based on these auditing principles, an understanding of the entire text of the principles is necessary. To achieve this, it may be helpful to consult the relevant financial audit standards (ISSAIs 2000-2899), performance audit standards (ISSAIs 3000-3899) and compliance audit standards (ISSAIs 4000-4899).

10) SAIs may choose to adopt the ISSAIs as their authoritative standards. In such cases the auditor must comply with all ISSAIs relevant to the audit. Reference to the ISSAIs applied may be made by stating:

... We conducted our audit[s] in accordance with the International Standards of Supreme Audit Institutions (ISSAIs).

In order to enhance transparency, the statement may further specify which auditing standards within the ISSAIs 2000-4899 the auditor has considered relevant and applied. This may be done by adding the following phrase:

The audit[s] was [were] based on ISSAI[s] xxx [number and name of the ISSAI or range of ISSAIs].

- 11) The International Standards on Auditing (ISAs) issued by the International Federation of Accountants (IFAC) are incorporated into the INTOSAI financial audit standards (ISSAIs 2000-2899). In financial audits, reference may therefore be made either to the ISSAIs or to the ISAs. The ISSAIs may provide additional public-sector application material, but the requirements upon the auditor in financial audits are the same. The ISAs constitute an indivisible set of standards and the ISSAIs in which they are incorporated may not be referred to individually. If the ISSAIs or the ISAs have been adopted as the SAI's standards for financial audits, the auditor's report should include a reference to those standards. This applies equally to financial audits conducted in combination with other types of audit.
- 12) Audits may be conducted in accordance with both the ISSAIs and standards from other sources provided that no contradictions arise. In such cases reference should be made both to the ISSAIs and to the other standards concerned.

3

FRAMEWORK FOR PUBLIC-SECTOR AUDITING

MANDATE

- 13) An SAI will exercise its public-sector audit function within a specific constitutional arrangement and by virtue of its office and mandate, which ensure sufficient independence and power of discretion in performing its duties. The mandate of an SAI may define its general responsibilities in the field of public-sector auditing and provide further prescriptions concerning the audits and other engagements to be performed.
- 14) SAIs may be mandated to perform many types of engagements on any subject of relevance to the responsibilities of management and those charged with governance and the appropriate use of public funds and assets. The extent or form of these engagements and the reporting thereon will vary according to the legislated mandate of the SAI concerned.
- 15) In certain countries, the SAI is a court, composed of judges, with authority over State accountants and other public officials who must render account to it. There exists an important relationship between this jurisdictional authority and the characteristics of public-sector auditing. The jurisdictional function requires the SAI to ensure that whoever is charged with dealing with public funds is held accountable and, in this regard, is subject to its jurisdiction.
- 16) An SAI may make strategic decisions in order to respond to the requirements in its mandate and other legislative requirements. Such decisions may include which auditing standards are applicable, which engagements will be conducted and how they will be prioritised.

PUBLIC-SECTOR AUDITING AND ITS OBJECTIVES

- 17) The public-sector audit environment is that in which governments and other public-sector entities exercise responsibility for the use of resources derived from taxation and other sources in the delivery of services to citizens and other recipients. These entities are accountable for their management and performance, and for the use of resources, both to those that provide the resources and to those, including citizens, who depend on the services delivered using those resources. Public-sector auditing helps to create suitable conditions and reinforce the expectation that public-sector entities and public servants will perform their functions effectively, efficiently, ethically and in accordance with the applicable laws and regulations.
- 18) In general public-sector auditing can be described as a systematic process of objectively obtaining and evaluating evidence to determine whether information or actual conditions conform to established criteria. Publicsector auditing is essential in that it provides legislative and oversight bodies, those charged with governance and the general public with information and independent and objective assessments concerning the stewardship and performance of government policies, programmes or operations.
- 19) SAIs serve this aim as important pillars of their national democratic systems and governance mechanisms and play an important role in enhancing public-sector administration by emphasising the principles of transparency, accountability, governance and performance. INTOSAI P-20 Principles of Transparency and Accountability contain INTOSAI core principles in this regard.
- 20) All public-sector audits start from objectives, which may differ depending on the type of audit being conducted. However, all public-sector auditing contributes to good governance by:
 - providing the intended users with independent, objective and reliable information, conclusions or opinions based on sufficient and appropriate evidence relating to public entities;
 - enhancing accountability and transparency, encouraging continuous improvement and sustained confidence in the appropriate use of public funds and assets and the performance of public administration;



- reinforcing the effectiveness of those bodies within the constitutional arrangement that exercise general monitoring and corrective functions over government, and those responsible for the management of publiclyfunded activities;
- creating incentives for change by providing knowledge, comprehensive analysis and well-founded recommendations for improvement.
- 21) In general, public-sector audits can be categorised into one or more of three main types: audits of financial statements, audits of compliance with authorities and performance audits. The objectives of any given audit will determine which standards apply.

TYPES OF PUBLIC-SECTOR AUDIT

22) The three main types of public-sector audit are defined as follows:

<u>Financial audit</u> focuses on determining whether an entity's financial information is presented in accordance with the applicable financial reporting and regulatory framework. This is accomplished by obtaining sufficient and appropriate audit evidence to enable the auditor to express an opinion as to whether the financial information is free from material misstatement due to fraud or error.

<u>Performance audit</u> focuses on whether interventions, programmes and institutions are performing in accordance with the principles of economy, efficiency and effectiveness and whether there is room for improvement. Performance is examined against suitable criteria, and the causes of deviations from those criteria or other problems are analysed. The aim is to answer key audit questions and to provide recommendations for improvement.

<u>Compliance audit</u> focuses on whether a particular subject matter is in compliance with authorities identified as criteria. Compliance auditing is performed by assessing whether activities, financial transactions and information are, in all material respects, in compliance with the authorities which govern the audited entity. These authorities may include rules, laws and regulations, budgetary resolutions, policy, established codes, agreed terms or the general principles governing sound public- sector financial management and the conduct of public officials.

- 23) SAIs may carry out audits or other engagements on any subject of relevance to the responsibilities of management and those charged with governance and the appropriate use of public resources. These engagements may include reporting on the quantitative outputs and outcomes of the entity's service delivery activities, sustainability reports, future resource requirements, adherence to internal control standards, real-time audits of projects or other matters. SAIs may also conduct combined audits incorporating financial, performance and/or compliance aspects.
- 24) Public-sector auditing is indispensable for the public administration, as the management of public resources is a matter of trust. Responsibility for the management of public resources in line with intended purposes is entrusted to an entity or person who acts on behalf of the public. Publicsector auditing enhances the confidence of the intended users by providing information and independent and objective assessments concerning deviations from accepted standards or principles of good governance.

All public-sector audits have the same basic elements: the auditor, the responsible party, intended users (the three parties to the audit), criteria for assessing the subject matter and the resulting subject matter information. They can be categorised as two different types of audit engagement: attestation engagements and direct reporting engagements.

ELEMENTS OF PUBLIC-SECTOR AUDITING

THE THREE PARTIES

- 25) Public-sector audits involve at least three separate parties: the auditor, a responsible party and intended users. The relationship between the parties should be viewed within the context of the specific constitutional arrangements for each type of audit.
 - <u>The auditor:</u> In public-sector auditing the role of auditor is fulfilled by the Head of the SAI and by persons to whom the task of conducting the audits is delegated. The overall responsibility for public-sector auditing remains as defined by the SAI's mandate.
 - <u>The responsible party</u>: In public-sector auditing the relevant responsibilities are determined by constitutional or legislative arrangement. The responsible parties may be responsible for the subject matter information, for managing the subject matter or for addressing recommendations, and may be individuals or organisations.
 - <u>Intended users</u>: The individuals, organisations or classes thereof for whom the auditor prepares the audit report. The intended users may be legislative or oversight bodies, those charged with governance or the general public.

SUBJECT MATTER, CRITERIA AND SUBJECT MATTER INFORMATION

- 26) Subject matter refers to the information, condition or activity that is measured or evaluated against certain criteria. It can take many forms and have different characteristics depending on the audit objective. An appropriate subject matter is identifiable and capable of consistent evaluation or measurement against the criteria, such that it can be subjected to procedures for gathering sufficient and appropriate audit evidence to support the audit opinion or conclusion.
- 27) The criteria are the benchmarks used to evaluate the subject matter. Each audit should have criteria suitable to the circumstances of that audit. In determining the suitability of criteria the auditor considers their relevance and understandability for the intended users, as well as their completeness, reliability and objectivity (neutrality, general acceptance and comparability with the criteria used in similar audits). The criteria used may depend on a range of factors, including the objectives and the type of audit. Criteria can be specific or more general, and may be drawn from various sources, including laws, regulations, standards, sound principles and best practices. They should be made available to the intended users to enable them to understand how the subject matter has been evaluated or measured.
- 28) Subject matter information refers to the outcome of evaluating or measuring the subject matter against the criteria. It can take many forms and have different characteristics depending on the audit objective and audit scope.

TYPES OF ENGAGEMENT

29) There are two types of engagement:

- In attestation engagements the responsible party measures the subject matter against the criteria and presents the subject matter information, on which the auditor then gathers sufficient and appropriate audit evidence to provide a reasonable basis for expressing a conclusion.
- In direct reporting engagements it is the auditor who measures or evaluates the subject matter against the criteria. The auditor selects the subject matter and criteria, taking into consideration risk and materiality. The outcome of measuring the subject matter against the criteria is presented in the audit report in the form of findings, conclusions, recommendations or an opinion. The audit of the subject matter may also provide new information, analyses or insights.

formaterte: Engelsk (Storbritannia)

30)	Financial audits are always attestation engagements, as they are based on financial information presented by the responsible party. Performance audits are normally direct reporting engagements. Compliance audits may be attestation or direct reporting engagements, or both at once. The following constitute the subject matter or the subject matter information in the three types of audit covered by the ISSAIs:

a) Financial audit: The subject matter of a financial audit is the financial position, performance, cash flow or other elements which are recognised, measured and presented in financial statements. The subject matter information is the financial statements.

ISSAI 100 - FUNDAMENTAL PRINCIPLES OF PUBLIC-SECTOR AUDITING

- b) Performance audit: The subject matter of a performance audit is defined by the audit objectives and audit questions. The subject matter may be specific programmes, entities or funds or certain activities (with their outputs, outcomes and impacts), existing situations (including causes and consequences) as well as nonfinancial or financial information about any of these elements. The auditor measures or evaluates the subject matter to assess the extent to which the established criteria have or have not been met.
- c) Compliance audit: The subject matter of a compliance audit is defined by the scope of the audit. It may be activities, financial transactions or information. For attestation engagements on compliance it is more relevant to focus on the subject matter information, which may be a statement of compliance in accordance with an established and standardised reporting framework.

CONFIDENCE AND ASSURANCE IN PUBLIC-SECTOR AUDITING

The need for confidence and assurance


31) The intended users will wish to be confident about the reliability and relevance of the information which they use as the basis for taking decisions. Audits therefore provide information based on sufficient and appropriate evidence, and auditors should perform procedures to reduce or manage the risk of reaching inappropriate conclusions. The level of assurance that can be provided to the intended user should be communicated in a transparent way. Due to inherent limitations, however, audits can never provide absolute assurance.

formaterte: Engelsk (Storbritannia)

formaterte: Engelsk (Storbritannia)

SSAI 1	100 - FUNDAMENTAL PRINCIPLES OF PUBLIC-SECTOR AUDITING	 formaterte: Engelsk (Storbritannia)	
Form	ns of providing assurance		
32)	Depending on the audit and the users' needs, assurance can be	formaterte: Engelsk (Storbritannia)	
	communicated in two ways:		
	Through opinions and conclusions which explicitly convey the level of		
	assurance. This applies to all attestation engagements and certain direct		
	reporting engagements.		
	In other forms. In some direct reporting engagements the auditor does		
	not give an explicit statement of assurance on the subject matter. In		
	such cases the auditor provides the users with the necessary degree of		
	confidence by explicitly explaining how findings, criteria and conclusions		
	were developed in a balanced and reasoned manner, and why the		
	combinations of findings and criteria result in a certain overall conclusion		
	or recommendation.		
Leve	Is of assurance		
33)	Assurance can be either reasonable or limited.	formaterte: Engelsk (Storbritannia)	
	Reasonable assurance is high but not absolute. The audit conclusion is		
	expressed positively, conveying that, in the auditor's opinion, the subject		
	matter is or is not compliant in all material respects, or, where relevant, that		
	the subject matter information provides a true and fair view, in accordance		
	with the applicable criteria.		
	When providing limited assurance, the audit conclusion states that, based		
	on the procedures performed, nothing has come to the auditor's attention		
	to cause the auditor to believe that the subject matter is not in compliance		
	with the applicable criteria. The procedures performed in a limited		
	assurance audit are limited compared with what is necessary to obtain		
	reasonable assurance, but the level of assurance is expected, in the auditor's		

professional judgement, to be meaningful to the intended users. A limited assurance report conveys the limited nature of the assurance provided.



ORGANISATIONAL REQUIREMENTS

35) SAIs should establish and maintain appropriate procedures for ethics and quality control

Each SAI should establish <u>the relevant ethical requirements</u> and maintain procedures for ethics and quality control on an organisational level that will provide it with reasonable assurance that the SAI and its personnel are complying with professional standards and the applicable ethical, legal and regulatory requirements. The existence of these procedures at SAI level is a prerequisite for applying national standards that are based on or consistent with the Fundamental Auditing Principles. *ISSAI 130 - Code of Ethics* and *ISSAI 140 - Quality Control for*-*SAIs*-defines the requirements of the ISSAIs and provide related application_material in this regard.

36) SAIs should establish and maintain a system of quality management

Each SAI should establish and maintain a system of quality management to provide it with reasonable assurance that the SAI carries out all audits and other work at a consistently high level of quality and in accordance with the ISSAIs or other relevant standards and applicable legal and regulatory requirements. A SAI's system of quality management generally addresses the following interconnected components in a continual and iterative manner:

- SAI's risk assessment process,
- Governance and leadership,
- Relevant ethical requirements,
- Acceptance, initiation, and continuance of engagements,
- Performing engagements and issuing audit reports,
- SAI resources,
- Information and communication, and
- Monitoring and remediation process.

The existence of a system of quality management at SAI level is a prerequisite for applying or developing national standards based on the

formaterte: Engelsk (Storbritannia)

ISSAI 1	Func defir	UNDAMENTAL PRINCIPLES OF PUBLIC-SECTOR AUDITING lamental Auditing Principles. ISSAI 140 - Quality Management for SAIs hes the requirements of the ISSAIs and provides related application erial in this regard.	formaterte: Engelsk (Storbritannia)
37)		should establish and maintain appropriate procedures for petency management	
	man assu fulfil	SAI should establish and maintain procedures for competency agement on an organisational level that will provide it with reasonable rance that the SAI's auditors have the competencies required to I their function in accordance with their mandates. The competency agement at an organizational level generally involve: Determining relevant competencies <u></u> Providing enabling human resource practices, Providing pathways for professional development and Assessing and monitoring competencies.	
	appl ^ı tal A	existence of procedures for competency management is a prerequisite for ying national standards that are based on or consistent with the Fundamen- uditing Principles. ISSAI 150 - Auditor Competence defines the requirements e ISSAIs and provide related application material in this regard.	

GENERAL PRINCIPLES

Ethics and independence

38) Auditors should comply with the relevant ethical requirements and be independent. Ethical principles should be embodied in an auditor's professional behaviour. The SAIs should have policies addressing ethical requirements and emphasising the need for compliance by each auditor. Auditors should remain independent so that their reports will be impartial and be seen as such by the intended users.

Auditors can find INTOSAI Core Principles on independence in the INTOSAI *P-10 Mexico Declaration on SAI Independence*. The key ethical principles of integrity, independence and objectivity, competence, professional behavior and confidentiality and transparency are defined in *ISSAI 130 Code of Ethics*, together with related requirements and application material.

Professional judgement, due care and scepticism

39) Auditors should maintain appropriate professional behaviour by applying professional scepticism, professional judgment and due care throughout the audit. The auditor's attitude should be characterised by professional scepticism and professional judgement, which are to be applied when forming decisions about the appropriate course of action. Auditors should exercise due care to ensure that their professional behaviour is appropriate.

Professional scepticism means maintaining professional distance and an alert and questioning attitude when assessing the sufficiency and appropriateness of evidence obtained throughout the audit. It also entails remaining openminded and receptive to all views and arguments.

Professional judgement implies the application of collective knowledge, skills and experience to the audit process. Due care means that the auditor should plan and conduct audits in a diligent manner. Auditors should avoid any conduct that might discredit their work. formaterte: Engelsk (Storbritannia)

formaterte: Engelsk (Storbritannia)

formaterte: Engelsk (Storbritannia)

41 1	00 - FUNDAMENTAL PRINCIPLES OF PUBLIC-SECTOR AUDITING		formaterte: Engelsk (Storbritannia)
			formaterte: Engelsk (Storbritannia)
uali	i <mark>ty controlmanagement</mark>		
0)	Auditors should perform the audit in accordance with the	т.	formaterte: Engelsk (Storbritannia)
•	procedures and requirements of the professional standards on		
	quality control management		
	An SAI's quality control policies and management procedures should		
	assign and define responsibilities for quality and quality management		
	of individual auditscomply with professional standards, the aim being to		
	ensure that audits are conducted at a consistently high level. Quality		
	control-management procedures should cover matters such as the		
	direction, review and supervision of the audit process and the need for		
	consultation in order to reach decisions on difficult or contentious matters.		
	Auditors can find further information in ISSAI 140 Quality Control-		
	Management for SAIs.		
dit	t team management and skills		
.)	Auditors should possess or have access to the necessary skills		formaterte: Engelsk (Storbritannia)
	The individuals in the audit team should collectively possess the		
	knowledge, skills and expertise necessary to successfully complete the		
	audit. This includes an understanding and practical experience of the type		
	of audit being conducted, familiarity with the applicable standards and		
	legislation, an understanding of the entity's operations and the ability		
	and experience to exercise professional judgement. Common to all audits is the need to recruit personnel with suitable qualifications, offer staff		
	development and training, prepare manuals and other written guidance		
	and instructions concerning the conduct of audits, and assign sufficient		
	audit resources. Auditors should maintain their professional competence		
	through ongoing professional development. ISSAI 150 - Auditor		
	Competence defines the organizational requirements of the ISSAIs and		
	provide related application material in this regard.		
	Where relevant or necessary, and in line with the SAI's mandate and the		
	applicable legislation, the auditor may use the work of internal auditors,		
	other auditors or experts. The auditor's procedures should provide a		
	sufficient basis for using the work of others, and in all cases the auditor		
	should obtain evidence of other auditors' or experts' competence and		
		21	
		Z 1	

ISSAI 100 - FUNDAMENTAL PRINCIPLES OF PUBLIC-SECTOR AUDITING

independence and the quality of the work performed. However, the SAI has sole responsibility for any audit opinion or report it might produce on the subject matter; that responsibility is not reduced by its use of work done by other parties.

The objectives of internal audit are different from those of external audit. However, both internal and external audit promote good governance through contributions to transparency and accountability for the use of public resources, as well as economy, efficiency and effectiveness in public administration. This offers opportunities for coordination and cooperation and the possibility of eliminating duplication of effort.

Some SAIs use the work of other auditors at state, provincial, regional, district or local level, or of public accounting firms that have completed audit work related to the audit objective. Arrangements should be made to ensure that any such work was carried out in accordance with public-sector auditing standards.

Audits may require specialised techniques, methods or skills from disciplines not available within the SAI. In such cases experts may be used to provide knowledge or carry out specific tasks or for other purposes.

Audit risk

42) Auditors should manage the risks of providing a report that is inappropriate in the circumstances of the audit

The audit risk is the risk that the audit report may be inappropriate. The auditor performs procedures to reduce or manage the risk of reaching inappropriate conclusions, recognising that the limitations inherent to all audits mean that an audit can never provide absolute certainty of the condition of the subject matter.

When the objective is to provide reasonable assurance, the auditor should reduce audit risk to an acceptably low level given the circumstances of the audit. The audit may also aim to provide limited assurance, in which case the acceptable risk that criteria are not complied with is greater than in a reasonable assurance audit. A limited assurance audit provides a level of assurance that, in the auditor's professional judgment, will be meaningful to the intended users.

formaterte: Engelsk (Storbritannia)

SAI 1	00 - FUNDAMENTAL PRINCIPLES OF PUBLIC-SECTOR AUDITING	formaterte: Engelsk (Storbritannia)
		formaterte: Engelsk (Storbritannia)
		1
ate	riality	
3)	Auditors should consider materiality throughout the audit process	formaterte: Engelsk (Storbritannia)
	Materiality is relevant in all audits. A matter can be judged material if knowledge	
	of it would be likely to influence the decisions of the intended users. Determining	
	materiality is a matter of professional judgement and depends on the auditor's	
	interpretation of the users' needs. This judgement may relate to an individual	
	item or to a group of items taken together. Materiality is often considered in	
	terms of value, but it also has other quantitative as well as qualitative aspects.	
	The inherent characteristics of an item or group of items may render a matter	
	material by its very nature. A matter may also be material because of the context	
	in which it occurs.	
	Materiality considerations affect decisions concerning the nature, timing	
	and extent of audit procedures and the evaluation of audit results.	
	Considerations may include stakeholder concerns, public interest, regulatory	
	requirements and consequences for society.	
<u>ocu</u>	mentation	
4)	Auditors should prepare audit documentation that is sufficiently detailed to	formaterte: Engelsk (Storbritannia)
	provide a clear understanding of the work performed, evidence obtained	
	and conclusions reached	
	Audit documentation should include an audit strategy and audit plan. It	
	should record the procedures performed and evidence obtained and support	
	the communicated results of the audit. Documentation should be sufficiently	
	detailed to enable an experienced auditor, with no prior knowledge of the	
	audit, to understand the nature, timing, scope and results of the procedures	
	performed, the evidence obtained in support of the audit conclusions and	
	recommendations, the reasoning behind all significant matters that required	

SSAI 100 - FUNDAMENTAL PRINCIPLES OF PUBLIC-SECTOR AUDITING	formaterte: Engelsk (Storbritannia)
	formaterte: Engelsk (Storbritannia)
Communication	
45) Auditors should establish effective communication throughout the	formaterte: Engelsk (Storbritannia)
audit process	
It is essential that the audited entity be kept informed of all matters relating	
to the audit. This is key to developing a constructive working relationship. Communication should include obtaining information relevant to the audit	
and providing management and those charged with governance with timely	
observations and findings throughout the engagement. The auditor may	
also have a responsibility to communicate audit-related matters to other stakeholders, such as legislative and oversight bodies.	
PRINCIPLES RELATED TO THE AUDIT PROCESS	
Planning an audit	
46) Auditors should ensure that the terms of the audit have been clearly established	formaterte: Engelsk (Storbritannia)
Audits may be required by statute, requested by a legislative or oversight	
body, initiated by the SAI or carried out by simple agreement with the	
audited entity. In all cases the auditor, the audited entity's management, those charged with governance and others as applicable should reach a	
common formal understanding of the terms of the audit and their respective	
roles and responsibilities. Important information may include the subject,	
scope and objectives of the audit, access to data, the report that will result from the audit, the audit process, contact persons, and the roles and	
responsibilities of the different parties to the engagement.	
47) Auditors should obtain an understanding of the nature of the entity/	
programme to be audited	

This includes understanding the relevant objectives, operations,

regulatory environment, internal controls, financial and other systems and business processes, and researching the potential sources of audit evidence. Knowledge can be obtained from regular interaction

24

with management, those charged with governance and other relevant stakeholders. This may mean consulting experts and examining documents (including earlier studies and other sources) in order to gain a broad

48) Auditors should conduct a risk assessment or problem analysis and revise this as necessary in response to the audit findings

understanding of the subject matter to be audited and its context.

The nature of the risks identified will vary according to the audit objective. The auditor should consider and assess the risk of different types of deficiencies, deviations or misstatements that may occur in relation to the subject matter. Both general and specific risks should be considered. This can be achieved through procedures that serve to obtain an understanding of the entity or programme and its environment, including the relevant internal controls. The auditor should assess the management's response to identified risks, including its implementation and design of internal controls to address them. In a problem analysis the auditor should consider actual indications of problems or deviations from what should be or is expected. This process involves examining various problem indicators in order to define the audit objectives. The identification of risks and their impact on the audit should be considered throughout the audit process.

49) Auditors should identify and assess the risks of fraud relevant to the audit objectives.

Auditors should make enquiries and perform procedures to identify and respond to the risks of fraud relevant to the audit objectives. They should maintain an attitude of professional scepticism and be alert to the possibility of fraud throughout the audit process.

50) Auditors should plan their work to ensure that the audit is conducted in an effective and efficient manner

Planning for a specific audit includes strategic and operational aspects.

<u>Strategically</u>, planning should define the audit scope, objectives and approach. The objectives refer to what the audit is intended to accomplish. The scope relates to the subject matter and the criteria which the auditors

formaterte: Engelsk (Storbritannia)

will use to assess and report on the subject matter, and is directly related to the objectives. The approach will describe the nature and extent of the procedures to be used for gathering audit evidence. The audit should be planned to reduce audit risk to an acceptably low level.

<u>Operationally</u>, planning entails setting a timetable for the audit and defining the nature, timing and extent of the audit procedures. During planning, auditors should assign the members of their team as appropriate and identify other resources that may be required, such as subject experts.

Audit planning should be responsive to significant changes in circumstances and conditions. It is an iterative process that takes place throughout the audit.

Conducting an audit

51) Auditors should perform audit procedures that provide sufficient appropriate audit evidence to support the audit report

The auditor's decisions on the nature, timing and extent of audit procedures will impact on the evidence to be obtained. The choice of procedures will depend on the risk assessment or problem analysis.

Audit evidence is any information used by the auditor to determine whether the subject matter complies with the applicable criteria. Evidence may take many forms, such as electronic and paper records of transactions, written and electronic communication with outsiders, observations by the auditor, and oral or written testimony by the audited entity. Methods of obtaining audit evidence can include inspection, observation, inquiry, confirmation, recalculation, reperformance, analytical procedures and/or other research techniques. Evidence should be both sufficient (quantity) to persuade a knowledgeable person that the findings are reasonable, and appropriate (quality) – i.e. relevant, valid and reliable. The auditor's assessment of the evidence should be objective, fair and balanced. Preliminary findings should be communicated to and discussed with the audited entity to confirm their validity.

The auditor must respect all requirements regarding confidentiality.

formaterte: Engelsk (Storbritannia)

formaterte: Engelsk (Storbritannia)

1	ISSAI 1	00 - FUNDAMENTAL PRINCIPLES OF PUBLIC-SECTOR AUDITING	 formaterte: Engelsk (Storbritannia)
			 formaterte: Engelsk (Storbritannia)
	52)	Auditors should evaluate the audit evidence and draw conclusions	
		After completing the audit procedures, the auditor will review the audit documentation in order to determine whether the subject matter has been sufficiently and appropriately audited. Before drawing conclusions, the auditor reconsiders the initial assessment of risk and materiality in the light of the evidence collected and determines whether additional audit procedures need to be performed.	
		The auditor should evaluate the audit evidence with a view to obtaining audit findings. When evaluating the audit evidence and assessing materiality of findings the auditor should take both quantitative and qualitative factors into consideration.	
		Based on the findings, the auditor should exercise professional judgement to reach a conclusion on the subject matter or subject matter information.	
	<u>Repo</u>	rting and follow-up	
	53)	Auditors should prepare a report based on the conclusions reached	formaterte: Engelsk (Storbritannia)
		The audit process involves preparing a report to communicate the results of the audit to stakeholders, others responsible for governance and the general public. The purpose is also to facilitate follow-up and corrective action. In some SAIs, such as courts of audit with jurisdictional authority, this may include issuing legally binding reports or judicial decisions.	
		Reports should be easy to understand, free from vagueness or ambiguity and complete. They should be objective and fair, only including information which is supported by sufficient and appropriate audit evidence and ensuring that findings are put into perspective and context.	

The form and content of a report will depend on the nature of the audit, the intended users, the applicable standards and legal requirements. The SAI's mandate and other relevant laws or regulations may specify the layout or

wording of reports, which can appear in short form or long form.

recommendations to enable remedial action.

Long-form reports generally describe in detail the audit scope, audit findings and conclusions, including potential consequences and constructive Short-form reports are more condensed and generally in a more standardised format.

» Attestation engagements

In attestation engagements the audit report may express an opinion as to whether the subject matter information is, in all material respects, free from misstatement and/or whether the subject matter complies, in all material respects, with the established criteria. In an attestation engagement the report is generally referred to as the Auditor's Report.

» Direct engagements

In direct engagements the audit report needs to state the audit objectives and describe how they were addressed in the audit. It includes findings and conclusions on the subject matter and may also include recommendations. Additional information about criteria, methodology and sources of data may also be given, and any limitations to the audit scope should be described.

The audit report should explain how the evidence obtained was used and why the resulting conclusions were drawn. This will enable it to provide the intended users with the necessary degree of confidence.

» Opinion

When an audit opinion is used to convey the level of assurance, the opinion should be in a standardised format. The opinion may be unmodified or modified. An unmodified opinion is used when either limited or reasonable assurance has been obtained. A modified opinion may be:

- Qualified (except for) where the auditor disagrees with, or is unable to
 obtain sufficient and appropriate audit evidence about, certain items in
 the subject matter which are, or could be, material but not pervasive;
- Adverse where the auditor, having obtained sufficient and appropriate audit evidence, concludes that deviations or misstatements, whether individually or in the aggregate, are both material and pervasive;
- *Disclaimed* where the auditor is unable to obtain sufficient and appropriate audit evidence due to an uncertainty or scope limitation which is both material and pervasive.

formaterte: Engelsk (Storbritannia)

formaterte: Engelsk (Storbritannia)

formaterte: Engelsk (Storbritannia)

formaterte: Engelsk (Storbritannia)

Where the opinion is modified the reasons should be put in perspective by clearly explaining, with reference to the applicable criteria, the nature and extent of the modification. Depending on the type of audit, recommendations for corrective action and any contributing internal control deficiencies may also be included in the report.

» Follow-up

SAIs have a role in monitoring action taken by the responsible party in response to the matters raised in an audit report. Follow-up focuses on whether the audited entity has adequately addressed the matters raised, including any wider implications. Insufficient or unsatisfactory action by the audited entity may call for a further report by the SAI.